No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
17	Exmet partition wall 4½″ thick with burnt brick in cement mortar 1 : 3 including plastering with cement mortar 1 : 4 reinforcement in every third course, etc., complete	S.ft.	0 12 0	819	
18	R.B.C. terrace of sufficient thickness and necessary reinforcement as per design, etc., complete	Sqr.	75 0 0	60·62	
19	Plain parapet walls 9″ thick, 2′ high as per design including plastering, etc., complete	R.ft.	1 0 0	471	
20	White and colour washing, two coats	Sqr.	0 4 0	146·62	
21	Flooring with stone jelly concrete in lime mortar 3″ thick 1½″ cement concrete top and plastering with red cement including expansion joints at 10′ apart, etc., complete as per specifications	Sqr.	20 0 0	62·48	
22	Painting with silicate paint, two coats	Sqr.	4 6 0	37·05	
23	Varnishing with best Gopal Varnish, two coats	Sqr.	3 8 0	15·90	
24	Burnt brick in cement mortar 1 : 2 for circular pillars as per existing design, plastering, etc., complete	Each	25 0 0	26	
25	Providing and fixing double R.S. girders 3″×6″ ×12 lbs. including hoisting, etc., over pillars of verandah	Cwt.	15 0 0	42·4	
26	Boxing the double girders with burnt brick in cement mortar with distant pipes and plastering the wire net with cement, etc., complete	R.ft.	0 8 0	396	
27	Providing, fixing and hoisting steel trusses for 20′ span as per existing design, 9′ apart with bed plates, etc., complete	Each	100 0 0	4	
28	Teakwood wrought and put up with wood oiling, etc., complete	C.ft.	4 4 0	104·55	
29	Roofing with 1st class Mangalore tiles on teak reepers with ceiling tiles, etc.	Sqr.	30 0 0	19·20	
30	Ridge tiles set in mortar and cement pointed.	R.ft.	0 10 0	60	
31	Teakwood eave boards 9″ wide as per design with painting	R.ft.	0 8 0	120	
32	Mortar bands over roof	R.ft.	0 4 0	120	
33	Teakwood finials and pendents	Each	2 0 0	6	
34	Constructing cement concrete "U" shaped drain alround	R.ft.	0 12 0	500	
35	Providing underground drains for outlet of water in courtyard	L. S.	200 0 0		
36	Dismantling the sides of old walls for joining the new wall and reconstructing with bond° slabs, etc.	L. S.	35 0 0		
37	Earthwork levelling, grounding and forming	L. S.	35 0 0		
38	Providing C.I. Rainwater pipes 4″ dia. including bends, heads, clamps, etc., complete	R.ft.	1 8 0	200	

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 26th March 1940.

The attention of the public is invited to the notification, published on pages 718-720, Part VI of the *Mysore Gazette*, dated 4th April 1940, calling for tenders for the work of improvements to entrance to Chikmagalur Town by widening the road and bridge across waste weir in 8/153 of Kadur-Mangalore Road at Chikmagalur.

The last date of receipt of tender in this office is 15th April 1940.

M. A. RAMANUJAM,
Executive Engineer.